

NORTHERN PACIFIC
 SAINT PAUL DIVISION - ST. PAUL, MINN.
 MISSISSIPPI STREET TERMINALS
 STATE OF MINNESOTA - BRUCE
 NO. 12 "A"

Estimate of cost of proposed construction of coal storage shed and scrap platforms. As per option of coal storage shed and scrap platforms. As per sketch dated November 20, 1915.

	LABOR	MATERIAL	TOTAL
<u>Coal Storage Shed</u>			
Lumber 2500 FEM fir 2H @ L \$8 M \$6	20.00	18.00	38.00
Lumber 2500 FEM fir @ L \$10 M \$12	65.00	102.00	167.00
Millwork	4.00	12.00	16.00
Hardware & iron	4.50	14.00	18.50
Roofing 8 squares @ L 60x M \$2.50	12.50	20.00	32.50
Painting 160 sq.yds. @ L 8x M 3x	12.86	4.80	17.66
Superintendence & Use of Tools	139.26	167.80	307.06
Engineering & Incidentals	13.94	15.94	29.88
<u>Scrap Platform</u>	153.20	167.80	321.00
Lumber 6000 FEM fir 2H @ L \$8 M \$6	48.00	36.00	84.00
Lumber 6000 FEM fir @ L \$8 M \$10	48.00	60.00	108.00
Hardware & iron	96.00	15.00	111.00
Superintendence & Use of Tools	9.60	111.00	120.60
Engineering & Incidentals	10.40	111.00	121.40
<u>SUMMARY</u>	118.00	111.00	229.00
Coal Shed			321.00
Scrap platform			227.00
Total cost proposed work			548.00

NOT JOINT ACCOUNT
 Division Engineer,
 St. Paul, December 3, 1915.
 L.Y.No. 600

W. J. ...
 Division Engineer.
W. J. ...



Proposed Scrap Iron Platform and
Shed for Coal Storage at Mississippi St.
St. Paul Minn.

St. Paul Div. Terminal Div.
N.P.R.V.

Office of Civil Eng. St. Paul, Minn. 55405
Scale 1/8" = 1'-0"
Drawing No. 100-1000-100
Date 10-1-1910